

# New England Aqua Ventus I

## US DOE *Advanced Technology Demonstration Program for Offshore Wind*

Dr. Anthony Viselli, PE  
(207) 581-2828  
anthony.viselli@maine.edu

Dr. Habib Dagher, PE  
(207) 581-2138  
hd@maine.edu



Ocean Renewable Energy Conference XIII  
September 18-19, 2018




# Outline

- Who We Are
- Project Overview
- Testing of Three Floating Wind Turbine Platforms
- Concrete Semi-submersible Technology (VturnUS)
- Project Status
- Next Steps

- Founded through the NSF in 1996
- 180 faculty, staff and students/year
- 100,000 ft<sup>2</sup> lab
- 2,000+ students funded from 35+ majors at UMaine
- 78 Spinoff companies

# Our Partners and Clients:



Ocean Renewable Energy Conference XIII  
September 18-19, 2018





# Over \$130 Million R&D

## Major Funding Agencies:



**NIST**  
National Institute of  
Standards and Technology  
U.S. Department of Commerce





# Wind Blade Research and Structural Testing



56m Gamesa blade  
(arriving 27 Aug  
2014)




Ocean Renewable Energy Conference XIII  
September 18-19, 2018





# National Level Test Facility: Wind Wave (W<sup>2</sup>) Ocean Engineering Laboratory

## Quality Wind and Wave Scaling



Ocean Renewable Energy Conference XIII  
September 18-19, 2018





Ocean Renewable Energy Conference XIII  
September 18-19, 2018




# Next-gen Scale Turbine Modeling

Carbon Fiber Blades

Flexible Shaft (in tower)


Motor/Controls (in base)



- Multi-scale offshore wind turbine capable of simulating a variety of commercial turbines of varying sizes (6-15MW+).
- Individual or collective blade pitch control.
- Carbon fiber blades
- Motor/controls mounted in hull.
- Light-weight tower top mass
- 3 m rotor diameter.


# Towing System

- 1m/s tow carriage speed
- Expandable to 5m/s





# Model Construction Equipment



5-axis CNC (4'x5'x8')




3D Printing (3'x3'x2')

# UMaine/ DOE Project Overview

Started 10 years ago!


- Demonstrate two x 6MW floating concrete turbines by 2021-2022
- VolturnUS floating concrete tech:
  - Lends itself to serial production
  - LCOE for utility-scale <7c/kWh
- Northeast US - dense population, high electricity costs and expanding electricity demand
- 55 Million in Northeast in an area no bigger than Texas!
- \$50.7M DOE Advanced Offshore Wind Technology Demonstration Program







# Key Accomplishments

- VoltturnUS concrete hull technology-reduced hull construction costs in US
- Site Control
- PPA Term Sheet 23c/kWh x 20 years
- ABS positive review of hull 100% FEED
- Successful 1:8 scale pilot deployment








2021 Construction Completed



Monhegan Island

### Latitude and Longitude of Site

Northern Boundary	43° 43' 18.231"
Eastern Boundary	69° 20' 16.759"
Southern Boundary	43° 42' 15.436"
Western Boundary	69° 17' 39.544"



## University of Maine Deepwater Offshore Wind Test Site



# 2010- Testing of Three Floating Wind Turbine Platforms




**3 Hulls, 60 Metocean Conditions, largest floating offshore wind data set made public.**

# UMaine Concrete Patented Hull Technology

Tap Existing US Concrete Infrastructure.

Domestic Production Low-cost 1 Hull per Week Serial Production



# PRECAST BRIDGE CONSTRUCTION SARAH MILDRED LONG BRIDGE - KITTERY, ME ON-SITE PRECAST TOWER SECTIONS





# Critical Technical Milestones Completed

- 1:8 Scale Prototype
- 1:50 Scale Model Tests of 100% FEED
- ¼ Scale Fabrication Effort
- ABS 100% FEED Approval

# VoltturnUS 1:8 Launch

## 1,600 Attended on May 31, 2013





Ocean Renewable Energy Conference XIII  
September 18-19, 2018






Ocean Renewable Energy Conference XIII  
September 18-19, 2018







Ocean Renewable Energy Conference XIII  
September 18-19, 2018




# Lessons from VoltturnUS 1:8 Pilot

## Validation of Technology Performance


Pilot saw 40 scaled 50 to 500-year return period storms:

- ✓ Max nacelle acceleration < 0.2g
- ✓ Max heel angle < 7degrees



# 1:50 Scale Test of 6MW Hull



## UMaine W2 Wave-Wind Basin



# 1:50 Scale Testing at UMaine

Confirmation of Design

50 year Extreme Waves with Turbine Operating





# ¼ Scale Mock Construction- 30 ton Concrete Structure Fatigue and Durability Testing



# ABS Hull 100% FEED Review

- **ABS has reviewed 28 design reports and data**  
and found 100% Hull FEED compliant

- **Primary Standard**


ABS Guide for Building

and Classing Floating


Offshore Wind Turbine Installations




Center Column Connection Front




Center Column Section Cut



DLC 6.1: 50-year Return Wave Event  
Ansys AQWA Potential Flow Model




DLC 6.1: 50-year Return Wave Event  
FEA Shell Model - von Mises Eq. Stress








# Over 16 Years of Metocean Data



## Metocean Buoy




- Metocean Buoy
  - Waves
  - Wind speeds
  - Current from surface to sea floor
  - Temp, pressure, and visibility
  - Scatter plots for fatigue design
- Land-based LiDAR on Monhegan
  - Deployed March 18, 2014
  - Verify AWS atmospheric models
- DeepCLiDAR
  - Wind cube mounted on UMaine buoy
  - Deployed in 2014-2015 for further site characterization



# 5-year Instrumentation and Monitoring Plan

## Key Objectives of Testing Plan:


- FOWT performance and design validation to support third-party certification efforts
- Validation of meteorological and ocean environments used in the design process
- FOWT numerical coupled model validation at a commercial scale
- System health monitoring to support operations and maintenance
- Support environmental monitoring as needed for permitting



# Pre-Deployment Environmental Studies

Extensive ecological, geotechnical, and cultural studies have been completed and are planned:

- Benthos: 2010-13, 2015
- Fish: 2010-15
- Marine Mammals: 2010-15
- Birds: 2010-15
- Bats: 2010-13, 2015
- Noise and Vibration: 2011, 2013
- Electromagnetic Fields: 2011, 2013
- Geophysical: 2010, 2013, 2015
- Terrestrial: 2014
- Aesthetics/Visual: 2013
- Cultural/Historic: 2010, 2014, 2015



# Outreach Activities

- Hundreds of meetings
- Island voted on July 26, 2016 – affirmative 39-1 to hire professional to complete community benefit agreement

# Timeline: New England Aqua Ventus I

- 2019 – PPA Contract Finalized and Design Complete
- 2020 – All Permits Received
- 2020 – Start Construction
- 2021 – Construction Completed





# Fierce Global Floating Wind Competition

## Examples:

- 2016 – France: three floating demonstration projects, each in the 24 MW range. Another project underway.
- 2016 – Portugal: approved 25 MW project
- 2018 – Scotland: 30 MW project
- 2017 – Japan: to deploy two additional demo hulls (in addition to 3 turbines off Fukushima) – 500GW potential.
- Germany - \$1Billion annual funding for offshore wind R&D- big focus on floating



# Questions?

Dr. Anthony Viselli, PE

(207) 581-2828

[anthony.viselli@maine.edu](mailto:anthony.viselli@maine.edu)

Dr. Habib Dagher, PE

(207) 581-2138

[hd@maine.edu](mailto:hd@maine.edu)

