



OCEAN RENEWABLE ENERGY CONFERENCE SEPTEMBER 19, 2018

# PELASTAR TLP TECHNOLOGY UPDATE

#### **GLOSTEN INTRODUCTION**

#### **Summary:**

- Established 1958
- 100 Employees
- Offices in Seattle, Boston, and New Bedford
- Naval Architecture, Marine Engineering and Ocean Engineering

Complete Vessel and Platform Design: Concept to Production Detailing

#### **Business Sectors:**

- Marine Construction
- Marine Energy (Oil & Gas)
- Oceanographic Research Vessels
- Ferries
- Aerospace and Special Projects
- Marine Renewable Energy and PelaStar









## PELASTAR TECHNOLOGY OVERVIEW

- PelaStar is the most technically-advanced FOWT TLP
- Centralized buoyancy, 5-arm, synthetic tendon design is optimal, cost-effective, and robust
- Received more 3rd party review than any other TLP concept
- Lowest utility scale cost of energy among all floating solutions
- Full-scale technology demonstration is our next step

Engineered for optimized deep-water commercial cost of energy



#### ADVANCED TENDON TECHNOLOGY

#### Synthetic Cable Tendons solve many of the traditional TLP mooring and installation challenges

- Minimize need to adjust tendon tensions to balance uneven loads at installation.
- Neutral buoyancy reduces overall system mass
- Tolerate slack-line events in extreme conditions.



## **MOORING AND ANCHORING**

#### PelaStar TLP


- Vertical Tendons
- Compact footprint
- Minimal impact on benthic ecology
- Minimal impact on fishing



## **MOORING AND ANCHORING**

#### **Catenary Spread Moorings**

- Extensive footprint
- Significant seabed impact



## ETI DEMO PROJECT FEED STUDY TEAM



Engineering, Integration, Cost and Management

Shipyard/ **Fabricator**  Various – to suit supply chain requirements



The Alstom Haliade 150, 6MW turbine is the **ALSTOM** first turbine to be integrated with the PelaStar foundation











Operations and Maintenance (O&M)







Anchor Fab and Installation

**Project Certification** 



## THE TECHNOLOGY SOLUTION


- TRL 5: Engineering-intensive FEED-level design with 6.0 MW turbine
- DNV GL approved Basis of Design and has reviewed the FEED-level design.
- 1:50 scale model tests performed with software validation reviewed and studied by DNV GL. Results co-published with DNV GL.
- Program total of USD 12 mil
  - USD 9 mil in engineering hours.



#### PELASTAR COST

Optimized for low commercial LCOE: PelaStar has the lowest primary steel weight for material and construction costs.

- Full cost analysis is available
- Recent reductions in bottom-fixed costs will transfer to floating wind and lower the floating wind baseline cost estimates further



2015 forecast – Updates will reflect current industry progress and wind farm development timescales.`

## **TECHNOLOGY DEVELOPMENT PARTERNS**



**Turbine Controls** 



**Tendon Technology** 





**Coupled Analysis** 



## INDUSTRIALIZED INSTALLATION METHOD

UK Patent Awarded - US Patent Imminent **Quayside Assembly** Installation Barge Engaged Foundation Pressed to Barge **Tow Out** PelaStar Support Barge Long-term utility-scale installation and deployment method utilizes a dedicated installation barge. **Transit to Site Tendons Installed To Preset Anchors** Installation Complete


## **NEW CLASS OF INSTALLATION VESSELS**

- DEME/GeoSea
  ORION
  - 3,000mt lift at 50m reach
  - 1,500mt lift on aux hook with 800mt heave compensation and 170m hook height
- Designed to transport and install next gen turbines
- Deep water floating lifts with no jack-up legs



#### LOADOUT: TURBINE/TOWER AND FOUNDATION

- Tow Foundation from fab yard to assembly site
- Bottom tower segment installed on Foundation with turbine equipment and pre-Commissioned
- Quayside assembly of turbine and blades on upper tower segments
- Orion lifts Turbine Assembly and Foundation onboard
- Transit to Site



## **INSTALL FOUNDATION**

- Foundation ballasted and lowered to tendon installation draft
- Tendons connected
- De-ballasted After Tendons Connected
- Tendon tensions verified
- Crane hook released
- Cleared Safe for boarding





## **INSTALL TURBINE / UPPER TOWER**

• Pick Weight: 700 MT, with Heave Compensation

Secure at Connection Joint with temporary latching devices


Release Crane Hook





#### **COMPLETE INSTALLATION**

- Complete permanent connection between the tower and Foundation
- Orion leaves: Estimated time on site:
  ~24hrs
- Final Commissioning and startup completed by wind farm support vessel



## PELASTAR: 6 MW, 12MW



	<b>12MW</b>	<u>6MW</u>
Min Water Depth:	100m	60m
Rotor Dia:	<b>220</b> m	150m
Hub Height abv. LAT	137m	108m
Tower Wt:	1,350mt	450mt
Column Diameter	10.5m	7m



#### **The PelaStar Team:**

**Bill Hurley** 

wlhurley@pelastar.com

**Ben Ackers** 

bbackers@glosten.com

Ken FitzGerald

klfitzgerald@glosten.com

